BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division, 17

SCHDULE-B

Name of Work: Improvements to Roads & Drain at Church Road L/S at Manjunathanagara in Bagalagunte Ward no.14 .Tdasarahalli sub division.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	202.80	81.00	Rupees Eighty One Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	30.42	3654.72	Rupees Three Thousand Six Hundred Fifty Four and Seventy Two Paise Only
3	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for beams, columns, staircase and roof with M-20(Cement-320 kg/cum) complete as per specifications.	Cum	63.88	5535.32	Rupees Five Thousand Five Hundred Thirty Five and Thirty Two Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	38.00	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	405.60	298.92	Rupees Two Hundred Ninety Eight and Ninety Two Paise Only
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	125.10	1600.00	Rupees One Thousand Six Hundred Only

Signature of the Contractor

Technical Manager(TM-2)

KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer

7	Providing and fixing Pre cast solid concrete kerb stones of size 450x150x500mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc. complete as per specifications.	No	3180.00	239.56	Rupees Two Hundred Thirty Nine and Fifty Six Paise Only
8	Providing and applying painting two coats (excluding priming coat) on new wood surface and/or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	Sqm	1908.00	76.68	Rupees Seventy Six and Sixty Eight Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per specifications.	Cum	202.80	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor
Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

EXECUTIVE ENGINEER,
Executive Engineer,
Dasarahalli Division,
Bruhat Bangalore Mahanagara Palike.
Dasarahalli Zone, Bangalore-57.